

TOWN OF LUNENBURG

RFP TOL2025011 – Fire Hall Apron

ADDENDUM #1 – Lunenburg Fire Hall Apron

1. Are we to include for 1000mm of structural fill for under the slab and the over excavation, removal and disposal of existing material that goes along with that?

A: Yes.

2. Who approves the structural fill?

A: The third party engineer, hired by the Town.

3. Drawing on the air percentage:

A: The air content specified for the cast-in-place concrete apron was 4% to 7%.

A: The apron will be exposed to chlorides, freezing, and thawing, for this exposure CSA recommends 5% to 8% air content