

TOWN OF LUNENBURG

TOL2025013

ADDENDUM #1 Pelham St Reconstruction

1. The curb detail on drawing C-001 shows what looks like two runs of rebar. It is hard to tell as these aren't labeled. This would be atypical for new curb and would be difficult to place as the new curb for this phase is all curved. Please confirm if these are runs of rebar? If so, please confirm if they are required? If they are required please indicate the size of the new rebar?

A: The rebar in the detail can be omitted.

2. Note 1 on drawing C-103 seems to indicate there may be some storm services within this phase of reconstruction that may need to be reconnected to the new storm or new sanitary. No pay item was provided for these services and no information regarding these services was provided. Please confirm reconnection of storm services is not part of this tender and if required will be extra to the contract?

A: The independent storm system is new and needs to be temporarily connected to the new sanitary system, which will remain a combined system until the system is eventually separated downstream on Prince Street. These new services are all included in the Tender Form (see 21, 23, 25, 31, 32, 33, 34).